INDIAN INSTITUTE OF MANAGEMENT SHILLONG

UMSAWLI, SHILLONG: 793018

MEGHALAYA

Fax No: 0364-2230041 **www.iimshillong.ac.in**

ENQUIRY NO: IIMS/S&P/NIQ/26-27/028 **Dated: 27.10.2026**

Sub: Notice Inviting Quotations for SITC of CCTV in Dam Site, IIM Shillong.

Offers are invited on behalf of Director, IIM Shillong from registered/ reputed dealer, supplier for tentative requirement of services addressed to the Director, IIM Shillong, Umsawli, Shillong-793018 with the subject "***Quotations for SITC of CCTV in Dam Site, IIM Shillong.***" Enquiry No. with due date and the offer to be sent by E-mail to **srmgr.stores@iimshillong.ac.in** latest by 3rd November 2026 by 12:00 noon

(Detailed Description)

Sr. No.	Description	Qty	Rate per unit (Inclusive of GST)	Amount (Inclusive of GST)
1	Supply, Installation, Testing and Commissioning of CAT-6 UTP (Unshielded Twisted Pair) outdoor Cable, 4 pair, 23 AWG solid bare copper conductors with inner sheath of FRPVC / Polyethylene, and outer sheath of flame retardant PVC (FR-PVC), with conductor DC resistance of 93.8 Ω/100 meters @ 20°C or more, resistance unbalance not exceeding 5%, mutual capacitance up to 5.6 nF/100 meters, capacitance unbalance (pair to ground) up to 330 pF/100 meters, nominal velocity of propagation (NVP) of 69%, impedance of 100 Ω ±15%, and worst-case cable skew of 45 ns/100 meters; the cable shall generally conform to ANSI/TIA-568.2-D standards and be suitable for 10GBASE-T Ethernet applications, Insulation Material: High density polyethylene (HDPE). These cables will be used for connecting CCTV and Network Switch.	250 Meters		
2	Supply, Installation, Testing and Commissioning of RJ 45 Connector on both the sides of CAT 6 Cable for STP Outdoor	15 Nos		
3	Supply, Installation, Testing and Commissioning of 4U Network Rack Basic Frame: Steel, Construction: Welded / CKD, Lockable Toughened Glass Door, Powder coated,	2 Nos		

	Rack Standard: Conforms to DIN 41494 or equivalent standard, Static Load: 30Kg, Dimensions: 258x550x500			
4	Supply, Installation, Testing and Commissioning of 8 Channel 4K Network Video Recorder with below specifications. • Instastream, H.265, H.264+, H.264, MJPEG Decoding • Resolution: 12MP, 8MP, 6MP, 5MP, 4MP, 3MP, 1080p, 720p, 960p, D1, CIF, QCIF • AI by NVR: Supports 4 Channel IMD • AI by Camera: Supports perimeter protection, IMD • Support 1 SATA HDD up to 20TB Each, 2 USB Ports, 1 HDMI, 1 VGA, 1 RJ45 • OEM developed mobile app and desktop Software. • Ethernet: 1 (10/100 Mbps Ethernet port, RJ-45), • IMD+ by NVR: 4 channels: Secondary filtering for human and motor vehicle, Reducing false alarms, • IMD+ by Camera: Human and vehicle detection on all channels, supporting up to 8 targets per second, • Network Bandwidth: 80 Mbps incoming, 80 Mbps recording and 60 Mbps outgoing, • Decoding Capability: AI disabled: 1 Channel 12MP@30 fps, 1 Channel 8MP@30 fps, 2 Channel 6MP@30 fps, 2 Channel 5MP@30 fps, 3 Channel 4MP@30 fps, 6 Channel 1080p@30 fps AI enabled: 1 Channel 8MP@30 fps, 1 Channel 6MP@30 fps, 1 Channel 5MP@30 fps, 2 Channel 4MP@30 fps, 4 Channel 1080p@30 fps, • Video Output: 1 HDMI: 3840 × 2160, 1920 × 1080, 1280 × 1024, 1280 × 720; 1 VGA: 1920 × 1080, 1280 × 1024, 1280 × 720, • Protocols: HTTP, HTTPS, TCP/IP, IPv4, IPv6, UDP, NTP, DHCP, DNS, SMTP, IP Filter, DDNS, InstaOn, Auto Connect, ONVIF (Profile T, Profile S, Profile G), CGI, SDK, • Recording Mode: General, Motion detection, Intelligent, Alarm, • Multi-channel Playback Up to 8 Channels.	1 Nos		
5	Supply, Installation, Testing and Commissioning of Network IR Bullet Camera, 1/2.8" 4MP PS CMOS Image Sensor (0.9071 centimeters), Max. 4MP (2688 × 1520)@1-30fps/ 4MP (2560 × 1440)@1-25/30, Instastream, H.265, H.264, H.264H, H.264B, MJPEG, Support Triple stream, WDR(120dB), Day/Night(ICR), 3D NR, AWB, AGC, BLC, HLC, 6mm Fixed Lens, Support Built-in Mic, IR Range of 60 Mtr., IP67, PoE, 128 MB RAM, 128 MB ROM, Support the classification and accurate detection of human, AES 256-bit Encryption, Configuration encryption, trusted execution, Digest, security logs, WSSE, account lockout, syslog, video encryption,	3 Nos		

	IP/MAC filtering, HTTPS, trusted upgrade, trusted boot, Certificates ISO 9001: 2015, ISO 20000-1 : 2018, CE, FCC and RoHS, BIS, STQC approved compliance report.			
6	Supply, Installation, Testing and Commissioning of Network IR Dome Camera, 1/2.9" 4MP PS CMOS Image Sensor (0.8758 centimeters), Max. 4MP (2688 × 1520)@1-25/30fps/ (2560 × 1440)@1-25/30, Instastream, H.265, H.264, H.264H, H.264B, MJPEG, Support Triple stream, WDR (120dB), Day/Night(ICR), 3D NR, AWB, AGC, BLC, HLC, Digital watermarking, 3.6mm Lens (2.8mm Optional), Support Built-in Mic, IR Range of 30 Mtr., IP67, PoE, 128 MB RAM, 128 MB ROM, Support the classification and accurate detection of human, AES 256-bit Encryption, Configuration encryption, trusted execution, Digest, security logs, WSSE, account lockout, syslog, video encryption, IP/MAC filtering, HTTPS, trusted upgrade, trusted boot, Certificates ISO 9001: 2015, ISO 20000-1 : 2018, CE, FCC and RoHS, BIS, STQC approved compliance report.	1 Nos		
7	Supply, Installation, Testing and Commissioning of 4 Ports Gigabit Unmanaged PoE Switch with 2 Gigabit Uplink Ports, PoE Power Budget: 48W.	1 Nos		
8	Supply, Installation, Testing and Commissioning of 8 Ports Gigabit Unmanaged PoE Switch with 2 Gigabit Uplink Ports, PoE Power Budget: 120W.	1 Nos		
9	Supply, Installation, Testing and Commissioning of Seagate/WD/Toshiba 2TB Surveillance Hard Disk	1 Nos		
10	Supply, Installation, Testing and Commissioning of 1KVA UPS.	1 Nos		
			Grand Total in Figures (Rs)	
	Grand Total in words			

<u>The above mentioned rates is inclusive of all taxes.</u>

Terms and Conditions:

1. No counter proposal is acceptable and conditional/late quotes are liable to be rejected.
2. Bidders should attach proof of similar works completed in the last three financial years along with copies of their PAN, GST etc

3. It will be the prerogative of the Institute to place the supply order for the whole lot/item or in piecemeal basis depending upon the requirement of the Institute. The Institute shall have the right to reject any tender without assigning any reason thereof. No correspondence will be entertained in this regard. Only one best quality item (according to our specification) should be quoted against the item.
4. Stores will be accepted subject to the verification and inspection by the competent authority.
5. Time schedule of delivery is within **30 days** of receipt of supply order or else deduction on gross bill @0.5% per week or part thereof will be made as liquidated damages/ delay in supply subject to maximum of 10% of the value of the delayed supplies.
6. Bills should be submitted in quadruplicate along with a receipted copy of challan duly endorsed in the desk of the of the Receiving section of the Institute.
7. Payment of the approved vendor for supply of items at IIM Shillong shall be made through cheque or electronic clearing system. In case of cheque, the same will be dispatched registered post and postal charges shall be deducted from their bills.
8. The Institute reserves the right to reject any tender or all tender without any reason.
9. Director, IIM Shillong or his authorized representatives shall be the final authority in setting all disputes and decision will be binding on all concerned.

Sd/-
Senior Manger Stores
IIM Shillong